



Clean Kerala Company Limited

A Government of Kerala Undertaking

No: E1/C-1448/DRRF/2023

Dated:08/12/2025

Notice Inviting Tender

Sub: - Fabrication and Installation of a self-supported Stainless Steel (SS) chimney of 250 mm diameter, constructed using a 12 mm MS base plate and 4 mm thick MS shell, with a total height of 22.5 meters at IPWMF Kunnamthanam, KINFRA Park - reg: -.

Sealed quotations are invited for the Fabrication and installation of a self-supported Stainless Steel (SS) chimney of 250 mm diameter, constructed using a 12 mm MS base plate and 4 mm thick MS shell, with a total height of 22.5 meters at IPWMF Kunnamthanam, KINFRA Park.

Scope of Work:

The work shall include, but not be limited to, the following:

- Fabrication and erection of the SS chimney structure
- Chimney hood
- C-ladder
- MS section flanges
- MS base plate
- Lightning arrester
- Ducting
- Hood
- Blower installation
- All required fittings, accessories, and supports
- Completion of all works with two coats of heat-resistant aluminium paint
- Execution of works as per standard engineering practices and PCB compliance norms.

Mechanical/Structural Work

Fabrication and assembly of the SS chimney sections

- Welding of MS/SS parts and flanges
- Installation of chimney hood, C-ladder, duct, and blower & Painting with heat-resistant aluminium paint.

Civil Work

- **Foundation work:**
 - Excavation for the base
 - Construction of reinforced concrete (RCC) foundation to support the chimney and base plate
 - Grouting and leveling of the base plate.

Registered Office : TC-29/1732, Second Floor, State Municipal House,
Vazhuthacaud, Trivandrum - 10, Kerala
CIN : U90000KL2013SGC035624

Phone : 0471-2724600 || Website : www.cleankeralacompany.com
Email : cleankeralacompany@gmail.com | info@cleankeralacompany.com

- **Anchor bolts and mounting:**
 - Installation of anchor bolts into the foundation
 - Proper alignment and leveling of the chimney base
- **Access platforms/landing pads** (if required) for maintenance

Electrical Work

- **Lightning arrester installation:**
 - Proper earthing and connection of lightning protection system
- **Blower and duct electrical connections:**
 - Power supply for blower operation
 - Cable laying and terminations for motors or sensors (if included)
- **Earthing of the chimney and metallic parts:**
 - Ensures safety against electrical faults or lightning strikes

Terms & Conditions:

1. The contractor/firm must have previous experience in chimney fabrication and installation.
2. Quoted rates should be inclusive of all materials, labour, tools, transportation, taxes, and incidental charges. The work shall conform to all relevant engineering, safety, and PCB standards.
3. The quotation shall remain valid for a period of 30 days from the date of submission.
4. The work shall be completed within the stipulated time after the issue of the work order.

Warranty:

1. The contractor shall provide a minimum 1-year warranty on all materials and workmanship from the date of completion.
2. Any defects, failures, or issues arising from materials or installation during the warranty period shall be rectified by the contractor at no extra cost.

Time of Completion : 30 Days
 Date of publishing the tender : 08/12/2025
 Last date for receipt of tender : 15/12/2025, 3.00 PM
 Date of opening of tender : 16/12/2025, 4 PM

Payment & other details

No Advance Payment
 Payment Method : RTGS/ NEFT
 Payment Terms : 100% of payment after completion of work.
 Document to be Submitted : GSTIN, License, Registration etc.
 For more details visit : www.cleankeralacompany.com

Phone No : 0471-2724600, 9446337912

Bank details

A/c No: 33622776812

IFSC : SBIN0007203

Bank : SBI Althara Branch

Thiruvananthapuram



Managing Director
Clean Kerala Company Limited
Thiruvananthapuram - 10


Managing Director

Clean Kerala Company Ltd