



Clean Kerala Company Limited

A Government of Kerala Undertaking

No: E2/CKCL/500/ 2025-MD.

Dated:02/12/2025

NOTICE INVITING TENDER

Sub: - Supply and installation of **wire mesh** at Muttathara DRRF near CAPE Engineering College, Thiruvananthapuram.- reg: -.

Sealed Tenders are invited for Supply and installation of **wire mesh** at Muttathara DRRF near CAPE Engineering College, Thiruvananthapuram. Work includes fabrication, fixing of posts, tensioning, and all necessary accessories.

Materials

1. Wire Mesh

- Material: Mild Steel (MS) / Galvanized Iron (GI) wire
- Wire gauge: 12 gauge (as per requirement)
- Mesh size: 50 mm × 50 mm (standard) or as specified
- Finish: Galvanized / PVC coated to prevent corrosion

2. Posts / Frames

- Material: MS pipe or angle iron, IS standard
- Size: 50 mm diameter / 50 × 50 × 5 mm angle
- Spacing: 2 m center-to-center (depending on design)
- Base plate for floor mounting: 150 mm × 150 mm × 6 mm thick (welded to posts)

3. Accessories

- MS clamps / fasteners to fix mesh to posts
- Tension wires at top and bottom for stability
- Nuts, bolts, washers (galvanized)
- Cement concrete base if required (M20) for posts

4. Fabrication & Installation

Registered Office : TC-29/1732, Second Floor, State Municipal House,
Vazhuthacaud, Trivandrum - 10, Kerala
CIN : U90000KL20135GC035624
Phone : 0471-2724600 || Website : www.cleankeralacompany.com
Email : cleankeralacompany@gmail.com | info@cleankeralacompany.com

- Wire mesh panels to be cut to required sizes and straightened before installation
- Panels to be fixed firmly to posts with bolts / clamps
- Tension wires to be installed at top and bottom of mesh for rigidity
- Posts to be erected vertically and aligned properly
- Bases of posts to be fixed either with anchor bolts or embedded in concrete
- Any sharp edges to be bent / capped for safety

5. Surface Treatment

- Galvanized mesh and posts for anti-corrosion protection
- Optional: Powder coating or PVC coating for additional durability and aesthetics

6. Quality Standards

- Wire mesh: IS 277 / IS 1020 compliant
- Steel posts: IS 2062 standard
- All fasteners and accessories to be galvanized
- Workmanship to be neat and aligned, with no loose fittings

7. Door / gate provision in mesh fencing

- Top barbed wire or angled extension for security

Time of Completion	- 30 Days
Date of Publishing	- 01/12/2025
Last date for receipt of tender	- 08/12/2025, 3 PM
Date of opening of tender	- 09/12/2025, 4 PM
EMD	- EMD @ 2.5 %

Note:

The rate may be quoted on a per square foot basis. The site should be visited before submitting the quotation.

Payment & other details

No Advance Payment

Payment Method - RTGS/ NEFT

Payment Terms - 100% payment will be made only after the successful completion of work.

Document to be Submitted - GSTIN, Proof of License & Registration etc.

Defect liability period - 3 Years

For more details visit - www.cleankeralacompany.com

Phone No - 0471-2724600, 9446337912

Bank details

A/c No - 33622776812

IFSC - SBIN0007203

Bank - SBI Althara Branch

Thiruvananthapuram


Managing Director
Clean Kerala Company Ltd.