



No: E1/C-1448/DRRF/2023

Dated:18/02/2026

## Notice Inviting Quotation

**Sub:** - Fabrication and Installation of a self-supported Mild Steel (MS) chimney of 250 mm diameter, constructed using a 12 mm MS base plate and 4 mm thick MS shell, with a total height of 18m height and 10m duct at IPWMF Kunnamthanam, KINFRA Park - reg: -.

Sealed quotations are invited for the Fabrication and installation of a self-supported Mild Steel (MS) chimney of 250 mm diameter, constructed using a 12 mm MS base plate and 4 mm thick MS shell, with a total height of 18m and 10m duct at IPWMF Kunnamthanam, KINFRA Park.

### Scope of Work:

The work shall include, but not be limited to, the following:

- Fabrication and erection of the MS chimney structure
- Chimney hood
- MS section flanges
- MS base plate
- Lightning arrester
- Ducting
- Hood
- Blower installation
- All required fittings, accessories, and supports
- Completion of all works with two coats of heat-resistant aluminium paint
- Execution of works as per standard engineering practices and PCB compliance norms.

### Mechanical/Structural Work

Fabrication and assembly of the MS chimney sections

- Welding of MS/SS parts and flanges
- Installation of chimney hood, C-ladder, duct, and blower & Painting with heat-resistant aluminium paint.

### Civil Work

- **Foundation work:**
  - Excavation for the base
  - Construction of reinforced concrete (RCC) foundation to support the chimney and base plate
  - Grouting and levelling of the base plate.

---

Registered Office : TC-29/1732, Second Floor, State Municipal House,  
Vazhuthacaud, Trivandrum - 10, Kerala  
CIN : U90000KL2013SGC035624

Phone : 0471-2724600 || Website : [www.cleankeralacompany.com](http://www.cleankeralacompany.com)  
Email : [cleankeralacompany@gmail.com](mailto:cleankeralacompany@gmail.com) | [info@cleankeralacompany.com](mailto:info@cleankeralacompany.com)

- **Anchor bolts and mounting:**
  - Installation of anchor bolts into the foundation
  - Proper alignment and leveling of the chimney base
- **Access platforms/landing pads** (if required) for maintenance

### **Electrical Work**

- **Lightning arrester installation:**
  - Proper earthing and connection of lightning protection system
- **Blower and duct electrical connections:**
  - Power supply for blower operation
  - Cable laying and terminations for motors or sensors (if included)
- **Earthing of the chimney and metallic parts:**
  - Ensures safety against electrical faults or lightning strikes

### **Terms & Conditions:**

1. The contractor/firm must have previous experience in chimney fabrication and installation.
2. Quoted rates should be inclusive of all materials, labour, tools, transportation, taxes, and incidental charges. The work shall conform to all relevant engineering, safety, and PCB standards.
3. The quotation shall remain valid for a period of 30 days from the date of submission.
4. The work shall be completed within the stipulated time after the issue of the work order.

### **Warranty:**

1. The contractor shall provide a minimum 1-year warranty on all materials and workmanship from the date of completion.
2. Any defects, failures, or issues arising from materials or installation during the warranty period shall be rectified by the contractor at no extra cost.

Time of Completion : 30 Days  
 Date of publishing the Quotation : 18/02/2026  
 Last date for receipt of Quotation : 21/02/2026, 3.00 PM  
 Date of opening of Quotation : 21/02/2026, 4 PM

### **Payment & other details**

No Advance Payment  
 Payment Method : RTGS/ NEFT  
 Payment Terms : 100% of payment after completion of work.  
 Document to be Submitted : GSTIN, License, Registration etc.

For more details visit : [www.cleankeralacompany.com](http://www.cleankeralacompany.com)

Phone No : 0471-2724600, 9446337912

**Bank details**

A/c No: 33622776812

IFSC : SBIN0007203

Bank : SBI Althara Branch

Thiruvananthapuram

S/d

**Managing Director**

**Clean Kerala Company Ltd**

**Approved from**

  
**Administrative Officer**  
**Clean Kerala Company Ltd**

